



Abbreviations

| | | | |
|--------|------------------------------------|---------|--|
| A/C | AIR CONDITIONING | LF | LINEAR FEET |
| AB | ANCHOR BOLT, AIR BARRIER | LH | LEFT HAND |
| ABM | AIR BARRIER MEMBRANE | LIB | LIBRARY |
| ABV | ABOVE | LIN | LINEAR |
| ACST | ACOUSTIC | LINO | LINOLEUM |
| ACT | ACOUSTICAL CEILING TILE | LKR | LOCKER |
| ADA | AMERICANS WITH DISABILITIES ACT | LL | LEAD LIN LINED |
| ADJ | ADJUSTABLE, ADJACENT | LLH | LONG LEG HORIZONTAL |
| AFT | ABOVE FINISHED FLOOR | LLV | LONG LEG VERTICAL |
| AFG | ABOVE FINISHED GRADE | LP | LOW POINT |
| AFS | ABOVE FINISHED SLAB | LPL | LOW PRESSURE LAMINATE |
| AGG | AGGREGATE | LR | LIVING ROOM |
| AHU | AIR HANDLING UNIT | LT | LIGHT |
| ALT | ALTERNATE | LTG | LIGHTING |
| ALUM | ALUMINUM | LWC | LIGHT WEIGHT CONCRETE |
| AMT | AMOUNT | LWIC | LIGHT WEIGHT INS CONCRETE |
| AP | ACCESS PANEL | | |
| APPD | APPROVED | MACH | MACHINE |
| ARCH | ARCHITECTURAL | MAS | MASONRY |
| ASPH | ASPHALT, ASPHALTIC | MAT | MATERIAL |
| AV | AUDIO VISUAL | MAX | MAXIMUM |
| ABM | AIR + VAPOR BARRIER MEMBRANE | MB | MACHINE BOLT |
| AVG | AVERAGE | MDF | MEDIUM DENSITY FIBERBOARD |
| @ | AT | MDO | MEDIUM DENSITY OVERLAY |
| | | MECH | MECHANICAL |
| B | BASEMENT, BASE | MED | MEDIUM, MEDICAL |
| BB | BULLETIN BOARD | MF | MINERAL FIBER |
| BD | BOARD | MFR | MANUFACTURER |
| BET | BETWEEN | MFR REC | MFR'S RECOMMENDATION |
| BEV | BEVELED | MH | MAN HOLE |
| BIT | BITUMINOUS | MIN | MINIMUM |
| RDG | BUILDING | MIRR | MIRROR |
| BLKG | BLOCKING | MISC | MISCELLANEOUS |
| BM | BENCH MARK, BEAM | ML | METAL LATH |
| BT | BOTTOM | MOLD | MOLDING |
| BRG | BEARING | MLWK | MILLWORK |
| BRK | BRICK | MO | MASONRY OPENING |
| | | MR | MOISTURE RESISTENT |
| C | COURSE | MS | MACHINE SCREW |
| CAB | CABINET | MTG | MOUNTED, MOUNTING |
| CAP | CAPACITY | MTL | METAL |
| CB | CHALK BOARD, CATCH BASIN, CNR BEAD | MW | MICROWAVE |
| CBG | CEMENTITIOUS BACKER BOARD | | |
| CER | CERAMIC | NAT | NATURAL |
| CEM | CEMENT | NIC | NOT IN CONTRACT |
| CHFR | CHAMFER | NFPA | NATL FIRE PROTECTION ASSN |
| CI | CAST IRON | NO | NUMBER |
| CJ | CONTROL JOINT | NOM | NOMINAL |
| CL | CENTER LINE | NTS | NOT TO SCALE |
| CLDG | CLADDING | | |
| CLG | CEILING | OA | OVERALL |
| CLO | CLOSET | OC | ON CENTER |
| CLR | CLEAR | OD | OUTSIDE DIAMETER |
| CM | CONSTRUCTION MANAGEMENT | OF/CI | OWNER FURNISHED / CONTRACTOR INSTALLED |
| CMFM | COLD FORMED METAL FRAMING | OH | OVERHEAD |
| CMT | CERAMIC MOSAIC TILE | OPNG | OPENING |
| CMU | CONCRETE MASONRY UNIT | OPP | OPPOSITE |
| CNR | CORNER | OPR | OPERABLE |
| CNTR | COUNTER | OS | OUTSIDE |
| COL | COLUMN | | |
| COMP | COMPRESSIBLE | PAR | PARALLEL, PARAPET |
| CONC | CONCRETE | PART | PARTIAL |
| CONST | CONSTRUCTION | PARTN | PARTITION |
| CONT | CONTINUOUS | PBD | PARTICLE BOARD |
| COORD | COORDINATE | PCC | PRECAST CONCRETE |
| CP | CAST IN PLACE | PERF | PERFORATED |
| CPT | CARPET | PERIM | PERIMETER |
| CT | CERAMIC TILE | PERP | PERPENDICULAR |
| CTK | COUNTERSUNK | PHS | PHILLIPS HEAD SCREW |
| CTR | CENTER | PL | PLATE, PROPERTY LINE |
| CU | COPPER, CUBIC | PLAM | PLASTIC LAMINATE |
| CUH | CABINET UNIT HEATER | PLAS | PLASTIC PLASTER |
| | | PLYWD | PLYWOOD |
| D | DRYER | PML | PANEL |
| DBL | DOUBLE | POLY | POLYETHYLENE, POLYURETHANE |
| DF | DRINKING FOUNTAIN | POLYISO | POLYISOCYANURATE INS BOARD |
| DH | DOUBLE HUNG | PREF | PREFINISHED PARTICLE BOARD |
| DIA | DIAMETER | PREFIN | PREFINISHED |
| DIM | DIMENSION | PT | PAINT, PRESSURE TREATED |
| DISP | DISPENSER, DISPOSAL | PTD | PAINTED |
| DM | DAMP PROOF MEMBRANE | QT | QUARRY TILE |
| DRW | DRAWER | | |
| DS | DOWNSPOUT | R | RADIUS, RISER |
| DTL | DETAIL | RB | RUBBER BASE |
| DV | DISHWASHER | RBR | RUBBER |
| DWG | DRAWING | RAD | RADIATOR |
| | | RC | RESILIENT CHANNEL |
| EA | EACH | RD | ROOF DRAIN |
| EIFS | EXTERIOR INS + FINISH SYSTEM | REC | RECESSED |
| EL | ELEVATION | RECP | RECEPTACLE |
| ELEC | ELECTRICAL | REF | REFERENCE |
| ELEV | ELEVATOR, ELEVATION | REFR | REFRIGERATOR |
| EPDM | ETHYLENE PROPYLENE DIENE MONOMER | REIN | REINFORCE, REINFORCING |
| EQ | EQUAL | REP | REPAIR |
| EQ SP | EQUALLY SPACED | REPL | REPLACE |
| EPS | EXPANDED POLYSTYRENE INS BOARD | REQD | REQUIRED |
| EW | EACH WAY | RESIL | RESILIENT |
| EWV | ELECTRIC WATER COOLER | RH | RIGHT HAND |
| EX | EXISTING | RL | RAIL LEADER |
| EXH | EXHAUST | RM | ROOM |
| EXP | EXPANSION, EXPOSED | RO | ROUGH OPENING |
| EXT | EXTERIOR | | |
| | | SAT | SUSPENDED ACOUSTICAL TILE |
| FA | FIRE ALARM | SC | SOLID CORE |
| FAS | FASCIA | SD | SMOKE DETECTOR |
| FC | FIRE CODE | SECT | SECTION |
| FCH | FURRING CHANNEL | SF | SQUARE FEET |
| FD | FLOOR DRAIN | SHF | SHELF |
| FDN | FOUNDATION | SHR | SHOWER |
| FE | FIRE EXTINGUISHER | SHRD | SHOWER DRAIN |
| FE EL | FRESH FLOOR ELEVATION | SHT | SHEET |
| FG | FIBERGLASS | SHTH | SHEATHING |
| FI | FLAT HEAD, FIRE HOSE | SHTV | SHEET VINYL |
| FIN | FRESH, FINISHED | SIM | SIMILAR |
| FIXT | FIXTURE | SJ | SCORED JOINT |
| FL | FLUSH | SKIT | SKYLIGHT |
| FLDG | FOLDING | SKFT | SPRAYED CELLULOSIC FIBER |
| FLR | FLOOR | SPECS | SPECIFICATIONS |
| FLSHG | FLASHING | SPRP | SPRINKLED FIREPROOFING |
| FLUOR | FLUORESCENT | SPKLR | SPRINKLER |
| FOF | FACE OF FINISH | SRUF | SPRAYED POLYURETHANE FOAM |
| FOM | FACE OF MASONRY | SO | SQUARE |
| FOS | FACE OF STUD OR SLAB | SS | SOLID SURFACING |
| ROW | FACE OF WALL | SST | STAINLESS STEEL |
| FP | FIREPROOF, FIREPROOFING | STD | STANDARD |
| FR | FIRE RATED, FIRE RESISTANT, FRAME | STL | STEEL |
| FRMG | FRAMING | STD | STORAGE |
| FSR | FLEXIBLE SHEET ROOFING | STRUCT | STRUCTURE, STRUCTURAL |
| FTG | FOOTING | SUP | SUPPORT |
| FURG | FURRING | SUSP | SUSPENDED |
| FURN | FURNISH, FURNITURE | SYM | SYMMETRICAL |
| PWC | FABRIC WALL COVERING | | |
| | | T | TREAD |
| GA | GAUGE | TB | THROUGH BOLT, TOWEL BAR |
| GALV | GALVANIZED | TEMP | TEMPERED |
| GB | GRAB BAR | TER | TERRAZZO |
| GC | GENERAL CONTRACTOR | THK | THICK |
| GDR | GUARD RAIL | THR | THRESHOLD |
| GRIC | GLASS FIBER REINFORCED CONCRETE | THRU | THROUGH |
| GFRG | GLASS FIBER REINFORCED GYPSUM | TKBD | TACKBOARD |
| GFRP | GLASS FIBER REINFORCED PLASTIC | TGB | TOP OF BEAM |
| GL | GLASS | TGC | TOP OF CONCRETE |
| GSB | GYPSUM SHEATHING BOARD | TOS | TOP OF STEEL |
| GT | GROUT | TOW | TOP OF WALL |
| GWB | GYPSUM WALL BOARD | TP | TOILET PAPER |
| GYP | GYPSUM | TR | TACK RAIL |
| GYP BD | GYPSUM BOARD | TSTAT | THERMOSTAT |
| GYP PL | GYPSUM PLASTER | TYP | TYPICAL |
| | | T&B | TOP AND BOTTOM |
| HB | HOSE BIBB | T&G | TONGUE AND GROOVE |
| HC | HANDICAPPED, HOLLOW CORE | T-Z CU | TIN ZINC COATED COPPER |
| HD | HEAD | | |
| HDDB | HARDBOARD | UC | UNDERCUT |
| HDR | HEADER | UDN | UNLESS OTHERWISE NOTED |
| HDW | HARDWARE | UPS | UNINTERRUPTIBLE POWER SUPPLY |
| HDWD | HARDWOOD | UR | URINAL |
| HGR | HANGER | | |
| HM | HOLLOW METAL | V | VINYL, VENT |
| HNDL | HANDRAIL | VCT | VINYL COMPOSITION TILE |
| HORIZ | HORIZONTAL | VERT | VERTICAL, VERTICALLY |
| HP | HIGH POINT | VEST | VESTIBULE |
| HPDL | HIGH PRESSURE DECORATIVE LAMINATE | VFP | VERIFY IN FIELD |
| HR | HOUR | VNR | VENEER |
| HSKG | HOUSEKEEPING | VP | VENER PLASTER |
| HT | HEIGHT | VRS | VAPOR RETARDER |
| HTG | HEATING | VWC | VINYL WALL COVERING |
| HW | HOT WATER | VWF | VINYL WALL FABRIC |
| | | W | WASHING MACHINE, WIDE |
| IBC | INTERNATIONAL BUILDING CODE | WB | WHITE BOARD |
| ID | INSIDE DIAMETER | WC | WATER CLOSET |
| INCL | INCLUSIVE | WD | WOOD |
| INS | INSULATION | WDW | WINDOW |
| INT | INTERIOR | WH | WATER HEATER |
| INV | INVERT | WM | WIRE MESH |
| IS | INSIDE | WP | WATERPROOFING |
| IWH | INSTANTANEOUS WATER HEATER | WPM | WATERPROOF MEMBRANE |
| | | WPO | WALL PROTECTION OVERLAY |
| JC | JANITORS CLOSET | WS | WOOD SCREW, WEATHERSTRIP |
| JBOX | JUNCTION BOX | WSC | WAINSCOT |
| JST | JOIST | WWF | WELDED WIRED MESH |
| JT | JOINT | W/ | WITH |
| | | W/O | WITHOUT |
| KC | KILN DRIED, KNOCKED DOWN | XPS | EXTRUDED POLYSTYRENE INS BD |
| KIT | KITCHEN | | |
| | | | |
| L | ANGLE | | |
| LAM | LAMINATED | | |
| LAV | LAVATORY | | |
| LBR | LUMBER | | |


Materials




UNDISTURBED EARTH




COMPACTED FILL




POROUS FILL




CONCRETE




FACE BRICK




CONCRETE BLOCK CMU




MORTAR / GROUT / DRYWALL




WOOD FRAMING - CONTINUOUS




WOOD BLOCKING OR SHIM




PLYWOOD




PARTICLE BOARD / MDF




FINISH WOOD




BATT OR LOOSE FILL INSULATON




BLOWN INSULATION




RIGID INSULATION



SHEET METAL



GLASS ELEVATION



ACOUSTICAL TILE

Cross State Office Building Lobby Renovations

Bureau of General Services
State House Station 77
Augusta, Maine 04333

SYMBOLS LEGEND

| | |
|--|---------------------------------|
| | EXISTING PARTITION OR WALL |
| | PROPOSED PARTITION |
| | CMU PARTITION OR WALL |
| | BRICK MASONRY VENEER |
| | PARTITION OR WALL TO BE REMOVED |
| | DOOR NUMBER |
| | PARTITION TYPE INDICATOR |
| | FRAME OR BORROWED LIGHT TYPE |
| | WINDOW TYPE |
| | LOUVER TYPE |
| | MILLWORK TYPE |
| | KEYED NOTE |
| | EXTERIOR ELEVATION INDICATOR |
| | INTERIOR ELEVATION INDICATOR |


DRAWING LIST

| | |
|--------|------------------------------------|
| G 100 | COVER SHEET |
| D 101 | DEMOLITION PLANS |
| A 101 | FLOOR PLANS |
| A 201 | REFLECTED CEILING AND FINISH PLANS |
| A 301 | INTERIOR ELEVATIONS |
| A 401 | INTERIOR DETAILS |
| ED 101 | ELECTRICAL REMOVALS PLAN |
| E 101 | ELECTRICAL PLANS |

Architect

Winton Scott Architects
5 Milk Street
Portland, Maine 04101

207-774-4811




Mark M. Wilcox

AUGUST 22, 2016

COVER SHEET

G 100



First Floor Demolition Plan
1/4"=1'-0"




REMOVALS LEGEND

--- TEMPORARY DUST PARTITION

REMOVALS KEYED NOTES

- 1 REMOVE EXISTING ALUMINUM FRAMED STOREFRONT. SAVE DOOR, HARDWARE AND ALUMINUM COMPONENTS FOR REUSE.
- 2 REMOVE EXIST CARPET AND GLUE. GRIND FLOOR SMOOTH FOR PROPOSED CARPET INSTALLATION.
- 3 REMOVE EXIST VCT AND GLUE. GRIND CONC SMOOTH FOR PROPOSED VCT INSTALLATION.
- 4 REMOVE EXIST METAL STUD FRAMED DRYWALL FASCIA FROM TOP OF STOREFRONT TO BOTTOM OF DRYWALL SOFFIT ABOVE.
- 5 WORKSTATION TO BE REMOVED BY OWNER.
- 6 REMOVE EXIST VCT AND GLUE. GRIND CONC SMOOTH AND PROVIDE LEVELASTIC SKIM COAT OVER ENTIRE AREA FOR PROPOSED VCT INSTALLATION.
- 7 REMOVE EXISTING HPDL COUNTER AND PREFABRICATE INTO TWO COUNTERS FOR INSTALLATION IN FINISHED SPACES.
- 8 REMOVE PROJECTING STRUCTURAL STEEL ANGLE COUNTER SUPPORT.
- 9 REMOVE EXISTING HPDL WALL PANELS, RUNNING WOOD TRIM AND TACK BOARDS ANP PATCH GWB SMOOTH. PATCH ANT PAINT ADJACENT WALLS EXACTLY. DO NOT DAMAGE EXISTING RETURN AIR GRILLE.
- 10 REMOVE EXIST RETURN AIR GRILLE AND REINSTALL FOLLOWING PROPOSED WALL FINISH WORK.
- 11 REMOVE EXIST MTL STUD/GWB PARTITION.
- 12 REMOVE EXISTING SUSP ACT CEILING. PATCH EXISTING ACT TO REMAIN TO MATCH EXISTING EXACTLY.
- 13 REMOVE EXISTING GWB CEILING BACK TO FRAMING IN PREPARATION FOR INSTALLATION OF NEW LOWER CEILING.



Third, Fourth + Fifth Floor Demolition Plans
1/4"=1'-0"



LEGEND

- EXISTING PARTITION
- EXISTING PARTITION OR ITEM TO BE REMOVED
- === PROPOSED PARTITION



Winton Scott Architects
5 Milk Street
Portland, Maine 04101
207.774.4811
www.wintonsscott.com

Architecture / Planning
Preservation Architecture
Interior Architecture




Mark M. Wilcox

State of Maine
Bureau of General Services
Augusta, Maine

Cross State
Office
Building
Renovations

Reception Areas At
Third/Fourth/Fifth Floors

Mail Room



AUGUST 22, 2016

Demo Plans


Scale: 1/4" = 1' - 0"

D 101



Winton Scott Architects
5 Milk Street
Portland, Maine 04101
207.774.4811
www.wintonsscott.com

Architecture / Planning
Preservation Architecture
Interior Architecture




Mark M. Wilcox

State of Maine
Bureau of General Services
Augusta, Maine

Cross State Office Building Renovations

Reception Areas At
Third/Fourth/Fifth Floors


Mail Room



AUGUST 22, 2016

Scale: 1/4" = 1' - 0"

A 101




First Floor Plan
1/4"=1'-0"

FINISH SCHEDULE

| ROOM NUMBER | ROOM | FLOOR | WALL BASE | WALL MATL | WALL FINISH | CEILING MATL | CEILING FINISH | NOTES |
|--------------|----------------|-----------|-------------|-----------|-------------|--------------|----------------|----------------|
| FIRST FLOOR | | | | | | | | |
| 101 | LOBBY | EXIST VCT | EXIST VINYL | -- | PTD | EXIST ACT | -- | |
| 103 | CONNECTOR | -- | -- | -- | -- | -- | -- | |
| 105 | MECHANICAL | -- | -- | -- | -- | -- | -- | |
| 105A | MAIL ROOM | VCT-2 | VINYL | GWB | PTD | ACT-1 | -- | |
| THIRD FLOOR | | | | | | | | |
| 301 | ELEVATOR LOBBY | VCT-1 * | -- | -- | PTD | -- | -- | * SEE D / A201 |
| 302 | WAITING | -- | -- | -- | PTD | -- | -- | |
| 303 | WAITING | -- | -- | -- | PTD | -- | -- | |
| 328A | RECEPTION | CPT | -- | -- | PTD | ACT-2 | -- | |
| FOURTH FLOOR | | | | | | | | |
| 401 | ELEVATOR LOBBY | VCT-1 * | -- | -- | PTD | -- | -- | * SEE D / A201 |
| 402 | WAITING | -- | -- | -- | PTD | -- | -- | |
| 403 | WAITING | -- | -- | -- | PTD | -- | -- | |
| 428A | RECEPTION | CPT | -- | -- | PTD | ACT-2 | -- | |
| FIFTH FLOOR | | | | | | | | |
| 501 | ELEVATOR LOBBY | VCT-1 * | -- | -- | PTD | -- | -- | * SEE D / A201 |
| 502 | WAITING | -- | -- | -- | PTD | -- | -- | |
| 503 | WAITING | -- | -- | -- | PTD | -- | -- | |
| 528A | RECEPTION | CPT | -- | -- | PTD | ACT-2 | -- | |


KEY
PTD AT EXIST WALL OR DOOR FRAME PAINT ONE COAT COLOR AND GLOSS TO MATCH EXISTING
EXIST EXISTING TO REMAIN




Third, Fourth + Fifth Floor Plans
1/4"=1'-0"

PARTITION TYPES


3" = 1'-0"



LEGEND
— EXISTING PARTITION
- - - - - EXISTING PARTITION OR ITEM TO BE REMOVED
= = = = = PROPOSED PARTITION




0 4 8




A First Floor Reflected Ceiling Plan
1/4"=1'-0"

Ceiling Legend




Sprinkler and Mechanical Keyed Notes

- 1 EXIST. SPRINKLER HEAD TO REMAIN @ 3RD AND 4TH FLOORS.
- 2 EXIST. SPRINKLER HEAD TO REMAIN @ 5TH FLOOR.
- 3 PROVIDE SPRINKLER HEAD TO MATCH EXISTING @ 3RD & 4TH FLOORS. FIELD VERIFY EXACT LOCATION.
- 4 PROVIDE SPRINKLER HEAD TO MATCH EXISTING @ 5TH FLOOR. FIELD VERIFY EXACT LOCATION.
- 5 REMOVE EXISTING RETURN AIR GRILLE AND SAVE FOR REUSE.
- 6 PROVIDE DUCTWORK OFFSET AND REINSTALL RETURN AIR GRILLE.



B Third, Fourth + Fifth Floor Reflected Ceiling Plans
1/4"=1'-0"




C Third, Fourth + Fifth Floor Wall Finish Plans
1/4"=1'-0"

FINISH LEGEND

- P1 MATCH EXIST WALL COLOR
VB1 6" BLACK VINYL BASE

VCT LEGEND

- F-1 FIELD TILE STONETEX PEBBLE GRAY 52122
B-1 BORDER TILE STONETEX COAL BLACK 52144



D Third, Fourth + Fifth Floor Flooring Pattern Plans
1/4"=1'-0"



Winton Scott Architects
5 Milk Street
Portland, Maine 04101
207.774.4811
www.wintonsscott.com

Architecture / Planning
Preservation Architecture
Interior Architecture




Mark M. Wilcox

State of Maine
Bureau of General Services
Augusta, Maine

Cross State
Office
Building
Renovations

Reception Areas At
Third/Fourth/Fifth Floors

Mail Room



AUGUST 22, 2016

Reflected
Ceiling and
Finish Plans


Scale: 1/4" = 1' - 0"

A 201



Winton Scott Architects
5 Milk Street
Portland, Maine 04101
207.774.4811
www.wintonscott.com

Architecture / Planning
Preservation Architecture
Interior Architecture



Mark M. Wilcox

State of Maine
Bureau of General Services
Augusta, Maine

Cross State Office Building Renovations

Reception Areas At
Third/Fourth/Fifth Floors







Mail Room

AUGUST 22, 2016





Interior Elevations

Scale: 3/8" = 1' - 0"

A 301




| DOOR & FRAME SCHEDULE | | | | | | | | | | | | | | | |
|-----------------------|---------------|-----------|----------|--------|------|----------|--------|------|---------|------|-----------|----------|----------------|---------|-----------------------|
| General | | | Door | | | Frame | | | Details | | | Hardware | Label | Remarks | |
| | | | | | | | | | | | | | | | |
| Door No. | Size (W x H) | Thickness | Material | Finish | Type | Material | Finish | Type | Head | Jamb | Threshold | | Label | Remarks | |
| 105A.1 | 3'-0" x 6'-8" | 1 3/4" | HM | PTD | D2 | HM | PTD | F2 | | | | | HW-1 | -- | |
| 301 | 3'-0" x 7'-0" | 1 3/4" | EX WD | * | D1 | ALUM. | F.F. | F1 | | | | | REUSE EXISTING | -- | * SAND + 2 COATS POLY |
| 401 | 3'-0" x 7'-0" | 1 3/4" | EX WD | * | D1 | ALUM. | F.F. | F1 | | | | | REUSE EXISTING | -- | * SAND + 2 COATS POLY |
| 501 | 3'-0" x 7'-0" | 1 3/4" | EX WD. | * | D1 | ALUM. | F.F. | F1 | | | | | REUSE EXISTING | -- | * SAND + 2 COATS POLY |
| | | | | | | | | | | | | | | | |





LEGEND

- HPDL PANEL BY MILLWORK
- PROVIDE ALUM STOREFRONT MULL TO MATCH EXIST
- LK-1 LITE KIT 1: NGB L-FRA100-SP BY GLASS & GLAZING - PAINT BY SECT 09 90 00

| GLAZING SCHEDULE | | | | |
|------------------|-------------|---------|-------------------|--------------------------|
| KEY | INSIDE | OUTSIDE | OVERALL THICKNESS | REMARKS |
| 1 | 3/8" LAM GL | -- | -- | SECURITY GLASS TYPE SG-1 |
| 2 | -- | -- | -- | HPDL PNL BY MILLWORK |




1 Mailboxes Enlarged Plan
3/4"=1'-0"




2 Mailboxes Section Detail
1 1/2"=1'-0"


| MILLWORK MATERIALS AND HARDWARE | |
|----------------------------------|---|
| HPDL STOREFRONT PANELS | PIONITE OR WILSONART 0.050" SUEDE FINISH |
| HPDL MAIL LOCKERS | PIONITE OR WILSONART 0.050" SUEDE FINISH |
| HPDL MAIL LOCKER CORES | 3/4" MDF |
| HPDL MAIL LOCKER INTERIORS | 3/4" LPL MDF - MELAMINE FINISHED WITH 3MM EDGEBANDING PANOLAM OR APPROVED EQUAL |
| 3MM PVC EDGING | CHARTER INDUSTRIES TO MATCH HPDL PROVIDE AT DOORS AND EXPOSED CASEWORK EDGES |
| SOLID SURFACING COUNTERS (SSM) | CORIAN -- COLOR GROUP C |
| MAIL LOCKER PULLS | AMEROCK #BP19001-SS STAINLESS STEEL 3" ARC PULL ONE PER COMPARTMENT |
| MAIL LOCKER HINGES | BLUM SERIES 125 ONE PAIR PER COMPARTMENT |
| MAIL LOCKER LOCKS + STRIKES | FURNISHED BE SECTION 08 70 00 INSTALLED BY MILLWORK ONE EACH PER COMPARTMENT |
| MAIL LOCKER NUMBER TAGS | SETON SIGNS #42611 + #42613 ONE PER COMPARTMENT |
| CORK | CLARIDGE 1/4" BURLAP BACKED CORK |



3 Mail Slot Section Detail
1 1/2"=1'-0"



4 Section Detail at Reception Storefront
1 1/2"=1'-0"



5 Enlarged Detail at Reception Storefront
3"=1'-0"



Winton Scott Architects
5 Milk Street
Portland, Maine 04101
207.774.4811
www.wintonscott.com

Architecture / Planning
Preservation Architecture
Interior Architecture



Mark M. Wilcox

State of Maine
Bureau of General Services
Augusta, Maine

Cross State Office Building Renovations

Reception Areas At
Third/Fourth/Fifth Floors



Mail Room

AUGUST 22, 2016































Interior Details

Scale: As Shown

A 401




- Electrical Removals Keyed Notes**
- 1 REMOVE EXISTING GREENFIELD DATA CONDUIT, SECURITY CONDUIT AND CABLING. GC PATCH CORE THRU 6" CONC SLAB TO MATCH EXISTING AND PATCH CPT TILE WITH MATERIAL FURNISHED BY OWNER.
 - 2 REMOVE EXISTING LIQUATITE POWER WHIP AND POKE THRU MONUMENT. SAVE FOR REUSE. REMOVE CABLING AND CONDUIT TO BRANCH CIRCUIT. GC PATCH CORE THRU 6" CONC SLAB TO MATCH EXISTING AND PATCH CPT TILE WITH MATERIAL FURNISHED BY OWNER.

| SYMBOLS LEGEND | | | | | |
|---|---|--|--|--|---------------------------------------|
| EXISTING ITEM TO REMAIN | EXISTING ITEM TO BE REMOVED PROVIDE BLANK STAINLESS STEEL PLATE | EXISTING ITEM TO BE REMOVED AND RELOCATED. PROVIDE BLANK STAINLESS STEEL PLATE | RELOCATED DEVICE | NEW DEVICE | DEVICE |
|  |  R |  RR | |  | DUPLEX OUTLET |
| | | | | | HARDWIRED CONNECTION |
|  | | | |  | VOICE/DATA OUTLET |
| |  R |  RR |  RL |  | CARD READER |
| | |  RR |  RL | | FRAME MOUNTED MAG LOCK |
|  |  R |  RR |  RL | | PUSH BUTTON MAG LOCK RELEASE |
| |  R |  RR | | | EMERGENCY MAG LOCK RELEASE |
| | |  RR |  RL |  | RTE PRESENCE SENSOR |
| | |  RR |  RL | | WALL MOUNTED EXIT SIGN |
| | | | |  | MOTION DETECTOR LIGHT SWITCH CLG MTD |
| | | | |  | SECURITY SYSTEM MOTION DETECTOR |
| | | | |  ES | ELECTRIC STRIKE FURNISHED BY HARDWARE |
| |  R |  RR |  RL |  DS | DOOR SWITCH |



Winton Scott Architects
5 Milk Street
Portland, Maine 04101
207.774.4811
www.wintonscott.com

Architecture / Planning
Preservation Architecture
Interior Architecture




State of Maine
Bureau of General Services
Augusta, Maine

Cross State Office Building Renovations

Reception Areas At
Third/Fourth/Fifth Floors

Mail Room




AUGUST 22, 2016

Electrical Demo Plans

Scale: 1/4" = 1' - 0"
































- ① PROVIDE DATA AND SECURITY CONDUIT AND CABLING AS SHOWN. GC PROVIDE CORE THRU 6" CONC SLAB AND TWO 2 HOUR FIRE STOP SYSTEM. FIELD VERIFY LOCATION.
- ② REINSTALL LIQUATITE POWER WHIP AND POKE THRU MONUMENT. EXTEND BRANCH CIRCUIT WIRING AND CONDUIT TO NEW LOCATION. RECONNECT POWER WHIP TO PROPOSED WORKSTATION. GC PROVIDE CORE THRU 6" CONC SLAB AND TWO 2 HOUR FIRE STOP SYSTEM. FIELD VERIFY LOCATION.
- ③ REINSTALL CARD READER AND EMERGENCY BREAKOUT. ELEC PROVIDE RECESSED CONDUIT AND BOXES. GC PROVIDE TRENCH AND PATCH THRU EXIST PLASTERED CMU WALL. GC PROVIDE TEMP OPENING AND PATCH THRU EXIST GWB SOFFIT ABOVE.
- ④ WIRE PROPOSED LIGHT FIXTURES TO EXISTING LIGHTING CIRCUIT IN OPEN OFFICE TO THE IMMEDIATE WEST.



| | Manufacturer | Model No. | Mounting | Lamping | Remarks |
|----|--------------|---|----------|---------|-----------------------------------|
| A | PEERLESS | MN9 1X1 G 80CRI 40K 1000LM DARK ZT 120 C041 | RECESSED | LED | 1 x 1 |
| EX | EXISTING | | | | PROVIDE MOTION DETECTOR SWITCHING |

1. MAINTAIN CIRCUIT CONTINUITY AT ALL TIMES. COORDINATE ALL WORK WITH THE OWNER'S ELECTRICIAN.
2. PROVIDE 48 HOURS ADVANCED NOTICE FOR ANY SHUTDOWNS.
3. SECURITY SYSTEM DEVICES, CABLING AND CONDUITS SHALL BE PROVIDED BY THE CONTRACTOR.
4. VOICE / DATA CABLING SHALL BE PROVIDED BY THE OWNER. THE CONTRACTOR SHALL PROVIDE THE PATHWAY FOR THE CABLING, INCLUDING SLAB CORING, CONDUIT SLEEVES, HANGERS AND FIRESTOPPING.




| SYMBOLS LEGEND | | | | | |
|---|---|---|---|---|---|
| EXISTING ITEM TO REMAIN | EXISTING ITEM TO BE REMOVED PROVIDE BLANK STAINLESS STEEL PLATE | EXISTING ITEM TO BE REMOVED AND RELOCATED. PROVIDE BLANK STAINLESS STEEL PLATE | RELOCATED DEVICE | NEW DEVICE | DEVICE |
|  |  |  | |  | DUPLEX OUTLET |
| | | | | | HARDWIRED CONNECTION |
|  | | | |  | VOICE/DATA OUTLET |
| |  |  |  |  | CARD READER |
| | |  |  | | FRAME MOUNTED MAG LOCK |
|  |  |  |  | | PUSH BUTTON MAG LOCK RELEASE |
| |  |  | | | EMERGENCY MAG LOCK RELEASE |
| | |  |  |  | RTE PRESENCE SENSOR |
| | |  |  | | WALL MOUNTED EXIT SIGN |
| | | | |  | MOTION DETECTOR LIGHT SWITCH CLG MTD |
| | | | |  | SECURITY SYSTEM MOTION DETECTOR |
| | | | |  | ELECTRIC STRIKE FURNISHED BY HARDWARE |
| |  |  |  |  | DOOR SWITCH |
| | | | |  | DURESS BUTTON BY SECURITY SUBCONTRACTOR |

===== EXISTING PARTITION
 - - - - - EXISTING PARTITION OF
 ITEM TO BE REMOVED
 ===== PROPOSED PARTITION



Architecture / Planning
Preservation Architecture
Interior Architecture




State of Maine
Bureau of General Services
Augusta, Maine

Cross State Office Building Renovations

Reception Areas At Third/Fourth/Fifth Floors

Mail Room



AUGUST 22, 2016

Electrical Plans

Scale: 1/4" = 1' - 0"